



SHORT URGENT QUOTATION NOTICE: 02 / EW / 2021

Memo No: 638 / EC / EW / 2021

Date: 09 / 11 / 2021

Sealed quotations for estimation purpose of following items per unit rate is hereby invited from the Manufacturers/ Distributors/ Dealers / Suppliers / Contractors up to / /2021 till 11:30 AM at IGIMS Patna. Agency can download the quotation from the institute website: www.igims.org and submit their quotation within schedule time by hard copy.

Date of obtaining quotation from the institute website: www.igims.org			09 /11 /2021 to 14/11 /2021		
Last Date , Time and Place for submission of quotation			15 /11/2021 up to 11.30 AM in the office of Executive Engineer (Electrical) IGIMS Patna through reg./ speed post/courier or by hand.		
Date & time of opening the received quotation			15 /11/2021 at 12:30 PM in the conference hall, IGIMS, Patna		
SI No.	Item descriptions	unit	Qty.	Rate/unit	Rate (In words)
1	SITC of 33kV grade Lighting arrestors at IGIMS, Patna.	Each	1.00		
2	SITC of 33 KV grade AB switch on the rail Pole at IGIMS, Patna	Each	1.00		
3	SITC of one no PT with PT ratio : 33000V / $\sqrt{3}$ / 110 / $\sqrt{3}$, for 33 KV HT Panel at IGIMS, Patna	Each	1.00		
4	SITC of one no PT with PT ratio : 11000V / $\sqrt{3}$ / 110 / $\sqrt{3}$ for 11 KV HT Panel at IGIMS, Patna	Each	1.00		
5	Removing of 13 meter rail pole from 33KV substation IGIMS, Patna	Each	1.00		
6	Shifting and Installation of OLTC in 33 KV substation at IGIMS, Patna	Each	1.00		
7	Oil-Filtrations of 33 and 11 KVA grade transformer (including transportation of filtration machine, BDV testing etc.)	Liter	1.00		
8	Supply of silica Gel	KG	1.00		

9	Painting of transformer from Painting gun machine	Each	1.00		
10	Supply of Transformer oil 11 KV grade Make- APAR, HP or equivalent	Barrel (209 ltr)	1.00		
11	Supply of Transformer oil 33 kv grade Make- APAR, HP or equivalent	Barrel (209 ltr)	1.00		
12	Supply and fixing of MS pipe 12 inch using insulation with 50mm thick loosely bound resin(LBR) mattress/mineral wool/ Rockwool density not 120kg/m2 and aluminum cladding (0.6mm) thick.	Meter	1.00		
13	Supply and fixing of MS pipe 10 inch using insulation with 50mm thick loosely bound resin(LBR) mattress/mineral wool/ Rockwool density not 120kg/m2 and aluminum cladding (0.6mm) thick.	Meter	1.00		
14	Supply and fixing of MS pipe 8 inch using insulation with 50mm thick loosely bound resin(LBR) mattress/mineral wool/ Rockwool density not 120kg/m2 and aluminum cladding (0.6mm) thick.	Meter	1.00		
15	Supply and fixing of MS pipe 6 inch using insulation with 50mm thick loosely bound resin(LBR) mattress/mineral wool/ Rockwool density not 120kg/m2 and aluminum cladding (0.6mm) thick.	Meter	1.00		
16	Supply and fixing of insulation with 50mm thick loosely bound resin(LBR) mattress/mineral wool/ Rockwool density not 120kg/m2 and aluminum cladding (0.6mm) thick on silencer of 250 KVA DG set.	Each	1.00		
17	Supply and fixing of insulation with 50mm thick loosely bound resin(LBR) mattress/mineral wool/ Rockwool density not 120kg/m2 and aluminum cladding (0.6mm) thick on silencer of 400 KVA DG set	Each	1.00		

18	Supply and fixing of insulation with 50mm thick loosely bound resin(LBR) mattress/mineral wool/ Rockwool density not 120kg/m2 and aluminum cladding (0.6mm) thick on silencer of 500 KVA DG set	Each	1.00		
19	Supply and fixing of insulation with 50mm thick loosely bound resin(LBR) mattress/mineral wool/ Rockwool density not 120kg/m2 and aluminum cladding (0.6mm) thick on silencer of 600 KVA DG set	Each	1.00		
20	Supply and fixing of insulation with 50mm thick loosely bound resin(LBR) mattress/mineral wool/ Rockwool density not 120kg/m2 and aluminum cladding (0.6mm) thick on silencer of 750 KVA DG set	Each	1.00		
21	Supply and fixing of SS bellow 12 inch using insulation with 50mm thick loosely bound resin(LBR) mattress/mineral wool/ Rockwool density not 120kg/m2 and aluminum cladding (0.6mm) thick.	Each	1.00		
22	Supply and fixing of SS bellow 10 inch using insulation with 50mm thick loosely bound resin(LBR) mattress/mineral wool/ Rockwool density not 120kg/m2 and aluminum cladding (0.6mm) thick.	Each	1.00		
23	Supply and fixing of SS bellow 8 inch using insulation with 50mm thick loosely bound resin(LBR) mattress/mineral wool/ Rockwool density not 120kg/m2 and aluminum cladding (0.6mm) thick.	Each	1.00		
24	Supply and fixing of SS bellow 6 inch using insulation with 50mm thick loosely bound resin(LBR) mattress/mineral wool/ Rockwool density not 120kg/m2 and aluminum cladding (0.6mm) thick.	Each	1.00		
25	Supplying and fixing of valve 1 inch dia	Each	1.00		
26	Supplying and fixing MS fuel pipe 1 inch dia	Meter	1.00		

27	Supplying and fixing of Diesel tank with MS stand capacity of 900 liter	Each	1.00		
28	Crane hireing charge for lifting of exhaust structure (complete 1 job)	Each	1.00		
29	Shifting and Installation of 11/0.433 KV transformer including foundation work	Each	1.00		
30	Shifting and Installation of 400 KVA DG set along with AMF Panel and control system including foundation work.	Each	1.00		
31	Shifting and Installation of 11 KV HT Panel including controlling system from panel to transformer.	Each	1.00		
32	Shifting and Installation of ACB Panel	Each	1.00		
33	Supply and fixing of 33 kv grade, high quality dilectric rubber mat of 5mm thickness (ISI Marked 15652:2006 With Genuine Test Certificate(BIS, CPRI, NTH & ERDA Approved)	Sqmt	1.00		
34	Insulation gloves for 33 kv grade, minimum length of 410mm and minimum thickness of 3.6mm to operate up to 36kv , bi-colour to meet ISI standard.	PAIR	1.00		
35	Insulation gloves for 33 kv grade minimum length of 410mm and minimum thickness of 3.6mm to operate up to 36kv , bi-colour to meet ISI standard.	PAIR	1.00		
36	Supply and Installation of 12 volt, 26 AH battery two years replacement warranty without any extra charge. Make- Excide, Luminous,etc.	Each	1.00		
37	Supplying and fixing 300 watt LED flood light with die cast Aluminum housing for ingress protection of IP65/IP66 and complete including connection , earthing the body and Making M.S Foundation for fixing light etc. as required	Each	1.00		

38	Installation charge for 1.5 /2 TR Split Air Condition	Each	1.00		
----	---	------	------	--	--

Note:- Quoted rate by the agency must include all complete works including supply, installation, testing and commissioning and taxes i.e GST or any taxes liable and contractor profit. The interested Quotationer /agency must visit the site (IGIMS, Patna) before quoting their rate.

Obtained quotations will be opened on scheduled date and time before the committee in the conference hall, IGIMS, Patna in presence of the bidders / agency or their representative.

Name:

**Sd/-
Executive Engineer (E)
IGIMS, Patna**

Address:

Signature of authorized agency:

Seal of the Firm: