

**INDIRA GANDHI INSTITUTE OF MEDICAL SCIENCES: SHEIKHPURA: PATNA-14**  
**BILL OF QUANTITIES**

1	Name of the work	Repair, Painting and Up Gradation of Indira Gandhi Memorial Park at IGIMS, Patna
2	Estimated cost	<b>Rs. 5,06,564/-</b> (Rs. Five lacs, Six thousand, Five hundred, Sixty Four only.
3	Cost of BOQ	Rs. 1250/- (Rs. One Thousand Two hundred fifty only)
4	Earnest Money Deposited	Rs. 10500/- (Rs. One Thousand Five Hundred only)
5	Time of Completion	30 days (Thirty)
6	Last date and time of receipt of tender	15-09-2015 up to 3.30 PM office of the Director, IGIMS, Patna-14 through Regt. /Speed Post/Courier Only.
7	Date and time of opening of Tender	16-09-2015 at 3.30 PM in Conference Hall, IGIMS, Patna

S N	Item Description	Unit	Qty.	Rate
1	Demolishing brick work including stacking of serviceable material and disposal of nserviceable material within 50 meters lead:In mud mortal	cum	5.62	149.80 Rs. One hundred forty nine & Paise eight zero only.
2	mortar 1 :4 (1 cement: 4 coarse sand ). Brick work with bricks of class designation 100A in foundations and plinth in : Cement	Cum	13.50	4184.00 Rs. Four thousand one hundred eighty four only.
3	Cement plaster in course sand 12 mm cement plaster of mix:1:4(1 cement :4 coarse sand)	Sqm.	168.00	100.30 Rs. One hundred & Paise three zero only.
4	Extra for providing and mixing water roofing material in proportion commended by the manufacturers 12 mm cement plaster 1:4(1 cement:3 sand)	Sqm	168.00	6.00 Rs. Six only.
5	With ready mixed zinc chromate yellow primer of approved brand and manufacture on steel galvanized iron/steel works	sqm	250.00	21.30 Rs. Twenty one & Paise three zero only.
6	Painting with ready mixed paint of approved brand and manufacture in all shades to give an even shade new steel work	sqm	250.00	60.70 Rs. Sixty & Paise seven zero only.
7	Removing dry or oil bound distemper by scrapping, sand paper and preparing the surface smooth luding necessary repari scratches tec. Gmplete	Sqm	498.52	5.40 Rs. Five & Paise four zero only.
8	Finishing walls with water proofing cement paint of approved brand and manufacture and of required shade to give an even shade New work (three or more coats).	Sqm.	500.00	60.50 Rs. Sixty & Paise five zero only.
9	Mirror polishing on marble work/stone work where ever required to give high gloss finish complete.	Sqm.	150.00	184.50 Rs. One hundred eighty four & Paise five zero only.

10	Providing and fixing M.S. grills of requirement pattern in frames of windows etc. with M.S. flats, square or round bars etc. All complete.	kg	3586.0 3	91.50 Rs. Ninety one & Paise five zero only.
11	Extra cost for carriage of Material			
b	Sone Sand (45 km from Koelwar)	Cum	19.24	545.80 Rs. Five hundred forty five & Paise eight zero only.
d	Bricks (7P+ 1K)	%o	6.39	476.50 Rs. Four hundred seventy six & Paise five zero only.
e	Difference of Cost of Bricks	%o	6.39	1088.90 Rs. One thousand eighty eight & Paise nine zero only.
f	Difference of Cost of Cement	tonn	2.00	818.35 Rs. Eight hundred eighteen & Paise three five only.

Quoted Rates:

- a- .....% above  
b- .....% below  
c- .....at estimated cost.

**NOTE:** - Contractors are requested to quote their rates % above / % below / at estimated rate  
In above format tenders quoting item wise rate will be rejected.

- 1- Issued to : - .....  
2- Full postal address : - .....  
3- Earnest money deposited : - .....  
4- Registration No. :- .....  
5- Time of completion : - .....

Signature of Contractors

Superintending Engineer  
I.G.I.M.S., Patna