

## Price bid for Short Tender/ QuotationNo.IGIMS/EW/80/2015-16

Bidders are requested to quote their lowest bid in each item

Repairing & Rewinding of 2 Nos ,500 KVA 11KV/440 volts Crompton Greaves Transformer installed at Main Sub station at IGIMS Patna-14					
Sr.no	Work description	Unit	Quantity	Quoted Rate ₹	Amount ₹
1	Dismantling of Top cover, radiator, relays , conservator tank & winding of transformer	set	2		
2	Cleaning of tanks & radiator	set	2		
3	Replacement of all Gaskets of top cover, radiator , conservator tank & silica gel	set	2		
4	Dismantling of Coil & Core from Winding (R,Y & B Phase)	each	6		
5	Manufacturing New Coil (HV & LV) as per actual	each	6		
6	Cleaning, Varnishing & Lamination of Core	set	2		
7	Assembly of coil in core	set	2		
8	Connection of winding as per actual	set	2		
9	Heating, Baking, Varnishing of all Coils	set	2		
10	Repairing of Buchholz relay	each	2		
11	Repairing of tap changer	each	2		
12	Replacement of oil temperature meter	each	1		
13	Repairing and replacement of Conservator gauge glass and diaphragm	each	2		
14	Assembly of Top cover, radiator relays, conservator tank & winding of Transformer	set	2		
15	Filtration of Transformer oil	Complete	2		

16	Supply of new Transformer oil as per IS-325	550 ltr/each transformer	2		
17	Testing of Transformer	set	2		
18	Loading, unloading shifting & transportation of transformer from site to repairing workshop (To and Fro) complete	set	2		
19	Supply of new pocelane Bushing with stud	set	2		
20	Spray painting of complete transformer	set	2		
	Total				
21	Miscillinius spares, and re commisioning of transformers.	10% of total cost	Lumpsum		
Total Rs					

Labour cess @ 1 %

Grand total ₹

Name Address of the Bidder -

Signature and Seal of the bidder

Date-