

INDIRA GANDHI INSTITUTE OF MEDICAL SCIENCES: SHEIKHPURA:

PATNA-14

BILL OF QUANTITY

01. **Name of the Work** - **Provision of vitreous floor tiles and Aluminium Sliding Window in college area (on all floors) of Nursing College Building at IGIMS, Patna**
01. Estimate Cost - 24,46,300=00 (RsTwenty four lacs forty six thousand three hundred only)
02. Earnest Money - Rs. 48,950/- (RsForty eight Thousand Nine Hundred Fifty Only.)
03. Cost of B.O.Q - Rs. 5000/- (Rs. Five Thousand only)
04. Time of Completion - 30 Days.
05. Last Date, time & place for submission of tender- 28 / 03 /2013 up to 3.00 PM at office of the Director, IGIMS,Patna-.14 through Regd./Speed Post /Courier
- 06 .Date and time for opening of tender (Technical Bid) 28 / 03 /2013 at 4.00 PM in Conference Hall, IGIMS, Patna
- 07- Date and time for opening of tender (Price Bid) - 30 / 03 /2013 at 12.30 PM in Conference Hall, IGIMS, Patna

Sl. No.	Item Description	Unit	Qty.	Rate/ Unit
1	Providing & Fixing aluminium glazed sliding window with 4.00 mm thick glazing of frost glass fitted on aluminium rail all complete as per specification and direction of EIC.	sqm	78.75	2959.00
2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS : 15622 of approved make in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	sqm	1623.00	1337.10

3	Deduct for not using 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) bedding in laying of floor tiles.	sqm	-1533.60	360.15
4	Fixing glazed/ Ceramic/ Vitrified floor tiles with cement based high polymer modified quick-set tile adhesive (Water based) conforming to IS: 15477, in average 3mm thickness	sqm	1533.60	336.75
5	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	920.00	9.20
6	Cement plaster in course sand 1:3 (1 cement:3 coarse sand)	sqm	400.00	94.50
7	Carriage of material			
a	Coarse Sand	cum	15.00	566.64

Quoted Rate –

- A) % above.
- B)% below
- C) At estimated Cost

Note: - Contractors are required to quote their rate in the prescribed Format as item wise rate .

- 01 Issued to – Name of Contractor -
-
- 02 Full Address -
- 03 E.M.D. Details - D.D. No----- Date ----- Amount-----
- 04 Registration Number -
-
- 05 Time of Completion -

Signature of Contractor with date

Superintending Engineer
I.G.I.M.S. Patna