

# INDIRA GANDHI INSTITUTE OF MEDICAL SCIENCES, PATNA-14

## BILL OF QUANTITY

SI. No.- 02 Tender Notice No.93 (C)/2016-17

Sl. No.	Name of the Work :-	Development Work in west Side of R.C.C. Block at IGIMS, Patna			
1	Estimated Cost (In Rs.) :-	Rs. 9,91,412.00			
2	Earnest Money (In Rs.) :-	Rs. 19,900/-			
3	Cost of B.O.Q. (In Rs.) :-	Rs. 1,250/-			
4	Time of completion :- ( In Days)	15 Days			
5	Last Date, time & place for submission of tender-	14/05/2016 up to 1:30 PM at office of the Director, IGIMS, Patna-14 through Regt. /Speed Post/Courier.			
6	Date and time for opening of tender-(Technical Bid)-	16/05/2016 at 3.30 PM in Conference Hall of IGIMS, Patna			
7	Date & Time for opening of Price Bid of technically Suitable bidders.	18/05/2016 at 3:30 PM			
Sl. No.	ITEM DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
<b>CIVIL WORK</b>					
1	Providing designation 100 A one brick on edge soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of E/I,	sqm	1,500.00	365.10	5,47,650.00
2	Supplying and Filling in plinth with local sand and under floors including, watering, ramming consolidating and dressing complete	Cum	554.00	192.50	1,06,645.00
3	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sqm and under including cutting the patch in proper shape and preparing and lastering the surface of the walls complete including disposal of rubbish to the dumping ground within 50 metres lead				-
a	With cement mortar 1:4(1 cement:4 coarse sand	sqm	78.00	150.10	11,707.80
4	Extra for providing and mixing water proofing material in proportion recommended by the manufacturers12 mm cement plaster 1:3(1 cement :3 sand)	Sqm.	78.00	7.50	585.00
5	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:	sqm	8.00	70.40	563.20
6	Finishing walls with water proofing cement paint of approved brand and manufacture and of required shade to give an even shade New work (three or more coats).	Sqm.	650.00	60.50	39,325.00
7	Extra cost for carriage of Material				-
A	Local Sand / Earth soil (3 Km)	Cum	554.00	205.29	1,13,730.66
B	Bricks (7P+ 1K)	%o	82.50	601.67	49,637.78
C	Difference of Cost of Bricks	%o	82.50	1,473.55	1,21,567.88
<b>Total Amount ( Rs.):-</b>					<b>9,91,412.31</b>
<b>PERMISSIBLE LIMIT UP TO 10% ("HIGH" OR "LOW")</b>					
<b>Quoted Rates:</b>					
a	.....% above				
b	.....% below				
c	.....at estimated cost.				
<b>NOTE:-</b>					

	<b>Contractors are requested to quote their rates % above / % below / at estimated rate</b>	
	<b>In above format tenders quoting item wise rate will be rejected.</b>	
<b>1-</b>	<b>Issued to</b>	
<b>2-</b>	<b>Full postal address</b>	
<b>3-</b>	<b>Earnest money deposited</b>	
<b>4-</b>	<b>Registration No.</b>	
<b>5-</b>	<b>Time of completion</b>	
	<b>Signature of Contractors</b>	<b>Superintending Engineer</b>
		<b>I.G.I.M.S., Patna</b>