

INDIRA GANDHI INSTITUTE OF MEDICAL SCIENCES, PATNA-14

BILL OF QUANTITY

Sl. No.- 06 Tender Notice No.93 (C)/2016-17

SI. No.	Name of the Work :-	Drilling of tube well.(size-5"x2") with Labour etc and supplying, installation Commissioning of submersible pump Proposed RHTC Maner IGIMS Patna-14
1	Estimated Cost (In Rs.) :-	Rs. 1,52,310.00
2	Earnest Money (In Rs.) :-	Rs. 3,100/-
3	Cost of B.O.Q. (In Rs.) :-	Rs. 500/-
4	Time of completion :- (In Days)	7 Days
5	Last Date, time & place for submission of tender-	14/05/2016 up to 1:30 PM at office of IGIMS, Patna-14 through Regt. /Speed
6	Date and time for opening of tender-(Technical Bid)-	16/05/2016 at 3.30 PM in Conference Patna
7	Date & Time for opening of Price Bid of technically Suitable bidders.	18/05/2016 at 3:30 PM

Non -Schedule Item

SI. No.	ITEM DESCRIPTION	UNIT	QUANTITY	RATE
SL.	DESCRIPTION	UNIT	QTY.	RATE
SUB HEAD -A				
1	Transportation of Boring Equipment Machine tools etc. including erection and dismantling and transporting back after completion of job.	L.S	1.00	
2	Construction of pit 20'x20'x6' for Storing water required for tubewell Drilling purpose.	Job	1.00	
3	Labour charges for boring of 300 mm Dia bore hole through any type of soil Boring is to be done by reverse /direct Circulation rotary system including Labour for boring and withdrawing all Drill and drill bit.	Feet	350.00	
4	Labour charges for lowering of tubewell pipe.	Feet	340.00	
5	Supply and fixing of Koderma origin Gravel.	Cft.	200.00	
6	Development charge of tubewell by air compressor till sand free discharge .	L..S.	1.00	
7	Supply of 5" dia PVC ISI mark pipe.	Feet	100.00	
8	Supply of 2" dia PVC ISI mark pipe.	Feet	180.00	
9	Supply of 2" dia PVC ISI mark Slotted pipe	Feet	100.00	
10	Small fitting like well cap well plug . Centre guide wire rope . Solvent cement etc.	L..S.	1.00	
(A)TOTAL AMOUNT (Rs):-				
SUB HEAD -B				
11	KSB Brand Submersible Pumpset. Pump Model CORA 7C / 10 + XUMA LX (s) 100 - 6/22 , No.of stage 08, Total Head 38 mtrs. , Discharge Capacity 8.500L/Hr., Liquid to be handled Clear Cold water free from sand and acid , Well dia 100 mm or above , outer let size 40 mm (1.5") , Motor Rating 1.5kw/2.0 Hp, Supply Voltage 200 volt (+/-10%) , Cable size 1 x 3 x 2.5 sq. mm			
a	Pumpset with 3 mtrs. Cable	each	1.00	
b	Supporting clamp 1.5" dia	each	1.00	
c	Estra cable size 1 x 3 x 2.5 sq. Mm	metre	30.00	
d	Control Panel	each	1.00	
e	Instalation and Commissioning charge	each	1.00	
f	1.5" dia G. I. 'B' Class pipe	feet	80.00	
g	1.5" dia G. I. Bend	each	1.00	
h	1.5" Gate Valve ISI mark	each	1.00	
(B)TOTAL AMOUNT :-(Rs):-				
(A+B)TOTAL AMOUNT (Rs):-				

PERMISSIBLE LIMIT UP TO 10% ("HIGH" OR "LOW")

Quoted Rates: for Schedule Item

a% above

b% below

cat estimated cost.

NOTE:- for Non Schedule Item.

Contractors are requested to quote their rates % above / % below / at estimated rate for Schedule Items ar rate for non schedule item (From- 1 to 11)

In above format tenders quoting item wise rate will be rejected.

1-	Issued to			
2-	Full postal address			:-
3-	Earnest money deposited			
4-	Registration No.			
5-	Time of completion			

Signature of Contractors

Superintending Engineer

I.G.I.M.S., Patna

4

all equipments
and
set at
4

the Director,
Post/Courier.

the Hall of IGIMS,

AMOUNT

AMOUNT
(IN Rs)

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

